


- A. 18" HDPE THREADED - VENTED MANWAY W/ 16" ACCESS, BLACK, W/ SS SCREWS (P/N 751016)
- B. TANK CALIBRATION AT 0° IN 100 GALLON INCREMENTS UP TO 500 GALLONS
- C. TANK FITTINGS TO BE INSTALLED AT TIME OF SHIPMENT AS PER DURA-CAST PROCEDURES

Weight: <small>Dependent on specific gravity rating</small>		NAME	DATE	 16160 Hwy 27 Lake Wales, FL. 33859		
Wall Thickness: <small>Dependent on specific gravity rating</small>	Drawn By:	S. Arant	8/20/2012			
Customer Part No: <small>N/A</small>	Customer APPR			Customer: Dura-Cast Products, Inc.		
Print Date: 8/28/2012	COPYRIGHT©2012 DURA-CAST PRODUCTS, INC.			Part Title: 900700 700 Gallon Vertical Tank		
Comments: - UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES - Std Radii 3/16"	UNLESS OTHERWISE SPECIFIED TOLERANCES ARE DIMS > 10" ±1% DIMS < 10" ±0.100 WALL THICKNESS ± 20% FLATNESS ± .030 in/in			File Name: 900700 700 Gallon Vertical Tank.dft		
				Size: A	Material: HDPE 942	Rev:
				Part No: 900700	Do Not Scale	Sheet: 1 OF 1